

Old Horticulture Cost Estimate

**COST ESTIMATE**

The cost estimate to remove the ACM in the Old Horticulture Building is provided in Table T-1.

**TABLE T-1  
ESTIMATED COST OF ABATEMENT OF ALL IDENTIFIED ACM**

<b>RECOMMENDED ACTION</b>	<b>UNITS</b>	<b>UNIT COST</b>	<b>ESTIMATED COST*</b>
Removal of 12" x 12" green floor tile with white streaks and associated mastic	2,409 s.f.	\$2.00/s.f.	\$4,818.00
Removal of fire door and frame	40 ct.	\$225.00/ea.	\$9,000.00
Removal of ceramic tile bedding compound	920 s.f.	\$6.00/s.f.	\$5,520.00
Removal of green chalkboards	11 ct.	\$100.00/ea.	\$1,100.00
Removal of roofing materials and products	15,000 s.f.	\$6.00/s.f.	\$90,000.00
Removal of window and door frame caulk compound	2,300 l.f.	\$4.00/l.f.	\$9,200.00
On-site air monitoring (asbestos)	7 days	\$600.00/day	\$4,200.00
Additional sampling of assumed ACM and selective demolition	2 days	\$600.00/day	\$1,200.00

**GRAND ESTIMATED TOTAL      \$125,038.00**

\* The cost estimates are based on current industry prices. Industry prices may change at any time. It is assumed that the work is performed by licensed, competent organizations. Estimates include all costs of abatement projects except replacement. Estimated cost is based on project size, difficulty, access, and all work being done at one time, etc.